



*From the MixCache.com library*

SAMPLE COPY

# Construction Quality Control and Commissioning

MixCache.com

SAMPLE COPY

## Table of Contents

- **Introduction**
- **Chapter 1** Foundations of Quality Control and Commissioning
- **Chapter 2** Codes, Standards, and Owner Project Requirements (OPR)
- **Chapter 3** Roles, Responsibilities, and Communication Protocols
- **Chapter 4** Preconstruction QA/QC Plans and Submittal Reviews
- **Chapter 5** Design-Phase Commissioning and Basis of Design (BOD) Alignment
- **Chapter 6** Construction-Phase Quality Assurance: Inspections and Checklists
- **Chapter 7** Factory and Site Acceptance Testing (FAT/SAT)
- **Chapter 8** Building Enclosure and Envelope Interfaces
- **Chapter 9** HVAC Functional Performance Testing
- **Chapter 10** Air and Hydronic Balancing (TAB)
- **Chapter 11** Electrical Power Systems Commissioning
- **Chapter 12** Lighting and Lighting Controls Verification
- **Chapter 13** Emergency Power and Life Safety Systems
- **Chapter 14** Plumbing, Domestic Water, and Drainage Systems
- **Chapter 15** Fire Protection and Fire Alarm Integration
- **Chapter 16** Building Automation Systems and Control Sequences
- **Chapter 17** Integrated Systems Testing and Interlocks
- **Chapter 18** Performance Acceptance Criteria and Measurement Methods
- **Chapter 19** Seasonal and Deferred Testing Strategies
- **Chapter 20** Indoor Environmental Quality: IAQ, Thermal Comfort, and Acoustics
- **Chapter 21** Energy Performance, M&V, and Analytics
- **Chapter 22** Documentation Standards: Checklists, Forms, and Templates
- **Chapter 23** Turnover Packages, Training, and Handover Readiness
- **Chapter 24** Warranty-Period Services and Issue Resolution
- **Chapter 25** Continuous Commissioning, Optimization, and Lessons Learned

## Introduction

Buildings succeed when they perform as intended for the people who occupy and operate them. Yet too often, projects reach substantial completion with unresolved defects, undocumented decisions, and systems that work only under ideal conditions. Construction Quality Control and Commissioning is written to close that gap. It provides a practical, field-tested framework for verifying performance, demonstrating handover readiness, and reducing warranty exposure—so owners receive facilities that run reliably from day one and practitioners have a repeatable process to deliver them.

This book treats quality control and commissioning as a single, integrated discipline that begins before the first submittal and continues through the warranty period. We connect the Owner Project Requirements and Basis of Design to day-to-day site activities, checkouts, and functional tests. By aligning design intent with measurable acceptance criteria, and by sequencing commissioning activities alongside construction, teams can detect issues earlier, resolve them faster, and document decisions clearly. The result is a smoother turnover, fewer post-occupancy complaints, and better long-term outcomes.

Readers will find detailed guidance on developing test plans and commissioning sequences for mechanical, electrical, plumbing, fire protection, and controls systems. We translate standards and best practices into actionable steps—what to test, when to test it, who witnesses, and what evidence proves compliance. Because many failures arise at interfaces, we devote special attention to integrated systems testing, envelope interactions, and the control logic that binds equipment together. Clear criteria and repeatable methods underpin every chapter.

Documentation quality is as important as technical execution. To streamline closeout, this book includes templates for inspections, start-up verifications, functional tests, deficiency tracking, training agendas, and turnover packages. Each template is designed to be concise in the field yet comprehensive enough to support handover, operations training, and warranty follow-up. We emphasize naming conventions, metadata, and version control so that owners receive a usable record set and commissioning authorities can maintain traceability.

Commissioning is ultimately a collaboration among owners, designers, contractors, and operators. We outline communication protocols, roles and responsibilities, and risk-based prioritization to focus effort where it matters most. The approach is scalable: whether you are delivering a small tenant fit-out or a complex healthcare facility, you can right-size the planning, testing depth, and documentation without compromising rigor. Practical examples and lessons learned, gathered from diverse building types,

help teams anticipate pitfalls and apply the methods with confidence.

Finally, the book addresses performance in operations—seasonal testing, measurement and verification, analytics, and continuous commissioning. Buildings change once occupied; loads shift, schedules evolve, and control sequences drift. By establishing clear acceptance thresholds, monitoring plans, and issue-resolution pathways during turnover, teams can manage that change proactively. Our goal is to equip you with systems—technical, procedural, and cultural—that verify performance, enable ready handover, and meaningfully reduce warranty claims.

SAMPLE COPY

## CHAPTER ONE: Foundations of Quality Control and Commissioning

Construction Quality Control and Commissioning is the discipline of proving that a building works the way it was intended, before the owner takes possession and the warranty clock starts ticking. It is not a single event or a last-minute inspection; it is a coordinated effort that begins with the first sketch of requirements and ends when the building consistently meets performance targets in real operation. The core idea is simple: measure twice, cut once, and document what you did so you can repeat it. When teams invest in verification early, they save costly rework later, shorten the punch list, and prevent the awkward conversations that happen when a system fails on opening day.

Quality control and commissioning are sometimes mistaken for each other, but they are complementary partners. Quality control is the set of practices that keep work within tolerances during installation—checking that the right equipment arrives, that it is installed per drawings, and that it is set up correctly before power is applied. Commissioning is the formal process of proving functional performance against agreed criteria. It turns drawings and specs into testable statements: “the air handler shall deliver 8,000 cfm at 1.2 in. w.c. at design cooling,” and it orchestrates the tests that prove it. When both are robust, the handover is not a leap of faith but a demonstration.

The business case is straightforward and measurable. Poor quality and incomplete commissioning produce callbacks, extended construction schedules, and higher operating costs. A missed fault in a variable air volume box can cause comfort complaints for months and waste energy. A single high-pressure steam leak during a winter startup can derail an entire facility opening. Owners pay for these problems twice: once during construction and again during operations. Commissioning reduces warranty exposure by making issues visible at the time of installation or startup and by documenting their resolution. It is risk management that pays for itself through avoided downtime and fewer warranty claims.

A foundational concept is the Owner Project Requirements, often called OPR. The OPR defines the owner’s goals in practical terms: occupancy types, environmental conditions, schedule constraints, maintainability expectations, and performance targets. Without a clear OPR, a building can be delivered “to spec” yet still miss the owner’s needs. The Basis of Design, or BOD, translates the OPR into technical strategies and systems. Commissioning uses these two documents as the measuring stick for every test. When the OPR says “frequent reconfiguration of lab spaces,” the

BOD should specify flexible utility distribution and accessible controls, and the commissioning plan should include tests for rapid changeover and safe isolation.

Commissioning is often described as a lifecycle, not a single phase. It starts in preconstruction with planning, moves through design with reviews and test planning, and intensifies during construction with inspections and functional testing. After substantial completion, it extends into the warranty period to ensure seasonal performance and early issue resolution. Finally, it informs continuous commissioning, where monitoring and tuning refine performance over time. This book follows that lifecycle because buildings are dynamic; a perfect startup in mild weather can reveal hidden flaws once the heating season arrives. Planning for that reality prevents surprises and supports reliable, long-term operation.

Success depends on people and protocols. Clear roles prevent the “not my job” problem. The owner defines the requirements and appoints a commissioning authority, the designer aligns the BOD and accepts test criteria, the contractor executes installation and participates in tests, and the operator is trained and involved early. Communication protocols identify who needs to be notified, who witnesses tests, and who signs off. Well-defined responsibilities and meeting rhythms keep everyone aligned and ensure that issues are resolved quickly rather than drifting into the turnover package as “open items.” Commissioning is a team sport, and the rules should be agreed at kickoff.

A robust Quality Assurance and Quality Control plan, often called a QA/QC plan, sets the ground rules for how work will be inspected and verified. It outlines procedures for submittal reviews, shop drawing checks, material receiving inspections, and pre-installation checks. It also defines acceptance criteria and the documentation required to prove compliance. A strong QA/QC plan prevents defects rather than merely discovering them. When linked with the commissioning plan, the QA/QC plan ensures that what is installed matches what will be tested, avoiding the classic disconnect where a system is built one way and then tested another way, producing confusing results and rework.

Submittals are the contractor’s promise that the proposed products and methods meet the contract requirements. A thorough review checks equipment schedules, performance curves, wiring diagrams, and control sequences against the specifications and the BOD. Commissioning teams often participate in these reviews to flag functional testing implications early. For example, if a pump submittal shows a fixed-speed unit while the spec calls for variable frequency drive control with soft start, the discrepancy will cause testing failures later. Catching it during submittal review prevents ordering the wrong equipment and keeps the project on track. The submittal register becomes a living tool linked to commissioning activities.

Early in the project, the commissioning authority develops a Commissioning Plan that

outlines scope, milestones, test procedures, and documentation requirements. It defines which systems are in scope, the sequence of testing, and who is responsible for each activity. The plan references specific test forms and acceptance criteria. It also establishes the schedule: when pre-functional checks happen, when functional performance tests occur relative to substantial completion, and how deferred or seasonal tests will be handled. A good plan reads like a playbook that any team member can follow, not a vague statement of intent. It sets expectations so that surprises are minimized during the execution phases.

Performance acceptance criteria are the measurable thresholds that determine whether a test is passed. They must be clear, realistic, and tied to the OPR and BOD. For instance, instead of “comfortable airflow,” the criteria might specify “between 7,500 and 8,500 cfm at 0.8 to 1.4 in. w.c. with supply air temperature within 2°F of setpoint.” Temperature, pressure, flow, power, and time are typical variables used. The criteria also define how many measurements to take, where to take them, and under what conditions. Ambiguity leads to disputes; precise criteria lead to faster approvals and smoother handover. Where possible, the team references industry standards to ground expectations.

The construction phase is where verification becomes tangible. Pre-functional inspections confirm that equipment is installed per approved submittals, that clearances are maintained, and that accessories like vibration isolators are correctly placed. Startup procedures verify rotation, lubrication, and initial power-up under supervised conditions. Functional tests then push systems to designed loads to verify controls integration and performance. Contractors often provide start-up reports; the commissioning team verifies that these reports exist and that the issues noted are resolved. The goal is to create a continuous chain of evidence from uncrating to full-load operation, with no unexplained gaps.

Integrated systems testing is where the building proves it can operate as a coordinated whole, not just a collection of individual pieces. This testing verifies interlocks between fire alarms and HVAC shutdowns, demand control ventilation tied to occupancy sensors, and emergency power transfer schemes. It checks sequences like “generator start within 10 seconds of utility loss, with non-critical loads shedding.” These tests often reveal surprises even when individual systems pass their tests, because timing and logic differences only appear when components interact. The commissioning plan must schedule these tests after subsystems are stable and assign clear roles for orchestration and observation.

Preventing post-occupancy issues starts with attention to interfaces and environmental conditions. The building envelope, for example, interacts strongly with mechanical systems; air leakage or thermal bridges can overwhelm HVAC capacity and cause moisture problems. Enclosure commissioning includes water penetration tests, air barrier continuity checks, and thermal imaging to find defects that would

otherwise manifest as mold or high energy bills. Similarly, indoor environmental quality tests for IAQ, thermal comfort, and acoustics confirm that the space is not just functional but habitable. Addressing these factors early avoids the “the building works, but no one likes it” outcome that leads to complaints and retrofits.

Documentation is the thread that ties everything together. A robust documentation standard specifies what forms to use, how to name files, and how to manage revisions. It ensures that test results are traceable to specific equipment, locations, and dates. Without these standards, handover packages become a jumble of PDFs with inconsistent naming, missing metadata, and unknown versions. The commissioning authority should establish a documentation dictionary and insist on consistent deliverables, such as a commissioning issue log, test reports with pass/fail criteria, and training records. Clear documentation reduces disputes, accelerates closeout, and enables effective operation and maintenance.

Training and handover readiness are the final gates before the owner takes control. Operators should be present during functional tests so they see how systems behave and learn troubleshooting steps. Training should be specific to the installed systems, not generic. The turnover package should include as-built drawings, equipment cut sheets, starting instructions, sequences of operation, and the commissioning test reports. A practical approach is to schedule a “dry run” handover where the commissioning team walks the owner through the documentation and demonstrates key functions. This step exposes gaps while there is still time to close them, avoiding the scramble that often accompanies final acceptance.

During the warranty period, the building continues to reveal its true performance under varied seasonal conditions and occupancy patterns. A structured warranty service plan sets expectations for issue reporting, response times, and correction verification. Many latent defects appear during the first heating or cooling season, making deferred and seasonal testing essential. The commissioning team should return to verify performance at design conditions and adjust setpoints or schedules as needed. Maintaining the commissioning issue log through this period helps differentiate between warranty items and operational changes, reducing disputes and ensuring that the owner is not paying for the contractor’s incomplete performance.

Continuous commissioning and optimization extend the value of the initial effort into ongoing operations. Buildings change: tenants reconfigure spaces, equipment ages, and control parameters drift. A continuous process uses trend data, analytics, and periodic retesting to identify deviations and improve performance. By establishing baselines during commissioning, owners can measure improvements and justify investments. The lessons learned from initial commissioning should feed back into the OPR and BOD for future projects. This loop turns commissioning from a project-phase activity into a culture of performance management, where verification and improvement are part of the building’s life.

To bring these foundations to life, it helps to step through a compact example. Imagine a mid-sized office building with variable air volume air handling units, a water-source heat pump plant, and a central building automation system. The OPR requires tight temperature control, high energy efficiency, and quiet spaces. The BOD specifies low-leakage VAV boxes, pressure-independent control, and extensive trend logging. The commissioning plan outlines pre-functional checks for each air handler, functional tests for VAV box airflow accuracy at multiple setpoints, and integrated tests for economizer changeover and night setback. The acceptance criteria state measured airflow within ten percent of setpoint and indoor noise below thirty-five decibels. The QA/QC plan requires vibration checks and filter inspections before startup. The contractor performs the startup and submits reports; the commissioning team verifies them. The integrated test checks that the fire alarm correctly shuts down the air handlers and that the generator carries essential loads. During warranty, a seasonal test confirms winter economizer performance. The documentation package includes an issue log showing that one noisy diffuser was replaced and a trend chart proving that supply air temperatures remain within setpoint during peak summer afternoons. The owner receives a clear record and an operating staff that knows the building because they participated in testing. The warranty claims are minimal, and the building meets its energy and comfort goals.

Establishing a common language and cadence for quality control and commissioning helps the entire project team coordinate effectively. The cadence is a repeating cycle of planning, doing, checking, and acting. Plans define what will be done and how success is measured. Doing is the installation and startup. Checking is the inspection and functional test. Acting is correcting deficiencies and updating documentation. When teams hold regular commissioning meetings to review open issues, upcoming tests, and schedule impacts, they prevent the “big bang” at substantial completion where all testing occurs at once and resources are strained. Incremental verification turns closeout into a series of small, manageable events rather than a frantic finish.

Industry standards and guidelines provide the technical backbone for commissioning and quality control. While the specifics of each standard can be dense, the core idea is consistent: define required tests, specify measurement methods, and set acceptable limits. For mechanical systems, standards address airflow measurement, hydronic balancing, and equipment startup. For electrical systems, they define power quality, protective device coordination, and testing of switchgear. For controls, they specify sequence verification and network diagnostics. The commissioning plan should reference the relevant standards and tailor them to the project’s scope, ensuring that test methods are credible, repeatable, and defensible. Using common standards also reduces friction during stakeholder reviews.

Risk management is embedded in the commissioning process by prioritizing tests based on impact and likelihood of failure. Life safety systems, critical power, and

environmental controls for health-sensitive spaces deserve extra attention and more witnesses. Lower-risk systems might rely on contractor testing with targeted commissioning verification. This risk-based approach focuses limited owner resources where failure would be most costly or dangerous. It also informs scheduling: high-risk tests occur earlier, allowing time for redesign or correction. By thinking in terms of risk, teams avoid over-testing simple systems and under-testing complex ones, achieving balanced coverage that matches the project's tolerance for risk.

The handover is more than a pile of documents; it is the transfer of knowledge and responsibility. A smooth handover requires that the owner's operations team is prepared to take control, that the documentation is organized and usable, and that the building has demonstrated performance under varied conditions. Acceptance should not hinge solely on substantial completion but also on successful completion of key functional tests. A practical gate is a "functional readiness review" where the commissioning authority certifies that systems are tested and documented, the owner confirms training is complete, and the issue log is at an agreed level of closure. This review turns a vague handover into a defined event.

Commissioning often reveals opportunities for improvement that go beyond fixing defects. When test results show a pump operating far from its best efficiency point, a simple sheave change can cut energy use. When control loops are oscillating, tuning can stabilize temperatures and reduce complaints. Documenting these optimization opportunities during commissioning helps owners prioritize post-occupancy improvements. It also sets the stage for continuous commissioning, where small adjustments yield large cumulative savings. By treating commissioning as a value-generating activity rather than a compliance exercise, teams align incentives and deliver better outcomes for owners, operators, and occupants alike.

From a practical standpoint, the tools of commissioning are simple but powerful: clear requirements, measurable criteria, coordinated plans, checklists, calibrated instruments, and disciplined documentation. A calibrated manometer or anemometer is as vital to the process as a good set of drawings. The act of measuring changes behavior; it forces the team to focus on what matters and to agree on what "good" looks like. When measurements are paired with traceable records, the building's behavior becomes knowable and manageable. This is the foundation that supports every subsequent chapter: a belief that performance can be specified, verified, and sustained through deliberate, well-documented effort.

Finally, commissioning is a cultural choice that values proof over assumption. It accepts that systems interact in unexpected ways, that equipment arrives with quirks, and that people make mistakes. Rather than deny these realities, the commissioning process plans for them. It creates checkpoints where surprises can be absorbed without catastrophe and where corrections are visible and agreed. By building this culture into a project, teams create the conditions for a successful handover and a

building that lives up to its promise. The chapters that follow translate this culture into concrete steps, test plans, and templates that can be used on real projects, day in and day out.

SAMPLE COPY

---

*This is a sample preview. Purchase the book to read the full content.*

Visit [MixCache.com](https://MixCache.com) to purchase the complete book.

SAMPLE COPY